Roads and Bridges Development Corporation of Kerala Ltd.(RBDCK) (A Government of Kerala Undertaking) 2nd floor, Preethi Building, M.V.RoadPalarivattom.Kochi 682025 Phone (484)2338205,2338206, Fax (91-484) 2533294 Website <u>www.rbdck.com</u> Email: - <u>rbdckltd@gmail.com</u>

OUOTATION NOTICE

Quotation No. RBDCK/ T259/ Vol I/ 156/ 2022

11/01/2022

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for the Repair and Maintenance Works of Sulthanpet ROB and Victoria College ROB in Palakkad District.

1.	Period of completion	-	10 days
2.	Date of issue of Schedule	-	11/01/2022
3.	Cost of document	-	Free of cost
4.	Last date and time of submission	-	17/01/2022, 3.00 PM
5.	Opening	-	17/01/2022, 4.00 PM

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 11/01/2022, 11.30 AM to 15/01/2022, 05:00 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

*Sd/-*General Manager

INSTRUCTIONS TO BIDDERS

- 1. Printed quotation forms can be obtained from the office of the undersigned and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc will be liable for summary rejection.
- 2. No quotations received after the specified last date and time will be accepted on any account.
- 3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any.
- 4. Each Bidder should submit along with the tender a signed copy of document in proof.
- 5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
- 6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities up to 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
- 7. Time is the essence of the contract. The work shall be completed within 10 days from the date of receipt of written order to commence the work.
- 8. Contractor shall appoint qualified engineering representative at site to supervise the work.
- 9. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other taxes including octroi on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 18% or as decided by the Government from time to time which will be paid in addition to the quoted rates.

Name and Signature of the Contractor

SPECIFICATIONS AND SCHEDULE OF WORKS:

Sl. No	Item	Unit	Quantity	Rate	Amount (Rs.)
1	Clearing grass and removal of rubbish up to a distance of 50 metres outside the periphery of the area				
		Hectare	0.17		
2	Man mazdoor engaged for clearing the drain and other cleaning works.				
		Day	5		
3	Providing, laying and rolling of close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.09 mm (Type-A) aggregates using viscosity grade bitumen (VG - 30) to the required line, grade, and level to serve as wearing course on a previously prepared base, including mixing in a suitable HMP of appropriate capacity not less than 75 tonnes/hour., laying and rolling with a Smooth wheeled roller 8-10 tonne capacity, and finishing to the required level and grade.		005		
		Sqm	885		
4	Providing and applying tack coat with bitumen emulsion(RS) using emulsion pressure distributor at the rate of 0.20 - 0.30 kg per sqm on the prepared bituminous surface cleaned with mechanical broom.		885		
5	Steel work for purlin/single section with G I pipes including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete	Kg	173.589		

6	Providing and fixing precoated galvanised iron				٦
	profile sheets (size, shape and pitch of				
	corrugation as approved by Engineer-in-				
	charge) $0.35 \text{ mm} (+0.05\%)$, total coated				
	thickness with zinc coating 120 grams per sqm				
	as per IS: 277, in 240 mpa steel grade, 5-7				
	microns epoxy primer on both side. of the				
	sheet and polyester top coat 15-18				
	microns.Sheet should have protective guard				
	film of 25 microns minimum to avoid				
	scratches during transportation and should be				
	supplied in single length up to 12 metre				
	or as desired by Engineer-in-charge. The sheet				
	shall be fixed using self-drilling/selftapping				
	screws of size (5.5x55mm) with EPDM seal,				
	complete up to any pitch in horizontal/vertical				
	or curved surfaces, excluding the cost of				
	purlins, rafters and trusses and including				
	cutting to size and shape wherever required.				
		Sqm	24.090		
7	Painting with synthetic enamel paint of				
	approved brand and manufacture to give an				
	even shade: Two or more coats on new work				
		Sqm	59.260		
	Total				

Dated Signature of Contractor: Name:

Address: