

RoadsandBridgesDevelopmentCorporationofKeralaLtd.(RBDCK)
(A Government of Kerala Undertaking)
2nd floor, Preethi Building, M.V.Road Palarivattom. Kochi 682025
Phone (484)2338205, 2338206, Fax (91-484) 2533294 Website www.rbdck.com Email: -
rbdckltd@gmail.com

QUOTATION NOTICE

Quotation No. **RBDCK/ T 330/ 232/ 2023**

01.03.2023

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for the Repair & Maintenance work of Kunhipalli ROB in Kozhikode District. The scope of work consists of Clearing & grubbing road and BC overlaying of Approach roads.

- | | |
|-------------------------------------|--|
| 1. Period of completion | - 20 days |
| 2. Date of issue of Schedule | - 02.03.2023 |
| 3. Cost of document | - Free of cost |
| 4. Estimate amount | - Rs. 0.20 lakhs (Approx. Including 18% GST) |
| 5. Last date and time of submission | - 10.03.2023, 4.00 PM |
| 6. Opening | - 13.03.2023, 11.30AM |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 02/03/2023, 1.00 PM to 10/03/2023, 04:00 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

Sd/-
General Manager

INSTRUCTIONS TO BIDDERS

1. Printed quotation form can be obtained from the office of the under signed and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc. will be liable for summary rejection.
2. No quotations received after the specified last date and time will be accepted on any account.
3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any.
4. Each Bidder should submit along with the quotation a signed copy of document along with copy of ID proof.
5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities up to 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
7. Time is the essence of the contract. The work shall be completed within 20 days from the date of receipt of written order to commence the work.
8. Contractor shall be solely responsible for any damages occurring to the existing road or any other structures due to this work.
9. Contractor shall appoint qualified engineering representative at site to supervise the work.
10. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other taxes including octroi on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 18% or as decided by the Government from time to time which will be paid in addition to the quoted rates.
11. The Defects liability period for the works is 06 months from the date of completion of the work.

12. The successful bidder shall deposit performance security for an amount equivalent to 3% of the quoted price before executing agreement.
13. In addition to Performance Security, retention money will be deducted from the running/ final bill of the contractor @ 2.5% of the gross amount of each running bill and same shall be released after expiry of defect liability period.

Name and Signature of the Contractor

SPECIFICATIONS AND SCHEDULE OF WORKS:

Sl. No	Item	Unit	Quantity	Rate	Amount (Rs.)
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 1000 metres including removal and disposal of top organic soil not exceeding 150 mm in thickness In area of light jungle - By Manual Means 				
		Hectare	0.079		
2	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 - For grading I Material				
		sqm	12.00		
	Total				

Dated Signature of Contractor:

Name:

Address: