

Roads and Bridges Development Corporation of Kerala Ltd. (RBDCK)
(A Government of Kerala Undertaking)
2nd Floor, Preethi Building, M.V. Road Palarivattom. Kochi 682025
Phone (484) 2338205, 2338206, Fax (91-484) 2533294 Website www.rbdck.com
Email: - rbdckltd@gmail.com

QUOTATION NOTICE

Quotation No .RBDCK/T 264/ Vol I/ 08 /2025

28.05.2025

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its General Manager invites sealed quotation for supply and planting demarcation stones along the alignment of Edachakkai-Nadakkavu ROB in Kasaragod District including Total Station Survey.

- | | | |
|-------------------------------------|---|---------------------|
| 1. Date of issue of Schedule | - | 28.05.2025 |
| 2. Cost of document | - | Free of cost |
| 3. Last date and time of submission | - | 09.06.2025, 2.00 PM |
| 4. Opening | - | 09.06.2025, 3.00 PM |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 28.05.2025, 4.00 PM to 09.06.2025, 01:30 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

Sd/-

General Manager

INVITATION FOR QUOTATION (IFQ)

1. Quotation is invited for the supply and planting of demarcation stones along the alignment of Edachakkai-Nadakkavu ROB in Kasaragod District.

Submission Guidelines

2. Suppliers/Contractors willing to undertake the work shall submit their quotations by filling out the attached BOQ
3. Printed quotation forms can be obtained from the office of the undersigned or the RBDCK website. Quotations submitted in formats other than the prescribed printed forms, or tenders that are incomplete (e.g., containing unattested errors and corrections), will be summarily rejected.
4. No quotations received after the specified last date and time will be accepted under any circumstances.
5. The cover of the sealed quotation shall be labelled as follows: **“Quotation for Total Station Survey and Boundary Stone Planting for Edachakkai-Nadakkavu ROB in Kasaragod District – Do not open before 09.06.2025 at 3:00 PM.”**
6. Each bidder shall submit a signed copy of the tender document along with proof of identity

Scope and Specifications

7. The specifications mentioned in the BOQ shall be strictly followed.
8. Details of the work, including item-wise specifications, are provided in the attached schedule of work. Bidders must quote only a single rate for each item in the schedule. The quoted rates shall be inclusive of all operations contemplated in the schedule of work and any incidental works necessary for such operations. The quoted rate shall remain fixed and shall not be subject to any variation, regardless of changes in quantity, if any.
9. The quoted rate shall be applicable for items in strict compliance with the specifications mentioned in the BOQ.

Work Execution

10. The date of the survey and planting of boundary stones shall be fixed in consultation with the engineer.

11. The planting of stones shall be completed on the same day or within three days of completing the survey work.
12. Following installation, a total station survey should be conducted to verify the positions of the stones. Additionally, details such as the number of boundary stones, stone-to-stone distances, coordinates, etc., must be clearly marked on the alignment drawing provided by this office and submitted to RBDCK without delay.
13. The contractor or their authorized representative must be present during the joint site inspection conducted by the Land Acquisition Officer and RBDCK based on this submitted drawing.

Payment Terms

14. The number of stones mentioned is indicative, and payment will be made based on the actual number of stones laid at the site. If planting a stone at a particular location is not possible, nail marking or paint marking shall be done at no extra cost.
15. The bill for the work will be sanctioned only after a joint inspection with the Revenue Department and subsequent approval from the Revenue Department.
16. If the stone planting work is partially completed and the remaining work is delayed for more than 30 days due to reasons not attributable to the contractor, part payment for the executed work may be released after withholding 10% as a security deposit. This deposit will be released along with the final payment upon completion of the work.
17. The quoted rate shall be inclusive of TDS, which will be deducted from the payment due to the contractor. The rates quoted by the contractor shall be deemed to include sales and other applicable taxes, including octroi, on all materials required for the execution of the contract. However, GST, as determined by the government from time to time, will be paid in addition to the quoted rates.

Responsibilities and Liabilities

18. In case the survey or demarcation stone planting is obstructed due to reasons such as objections from landowners, the work shall resume after resolving such issues without any additional cost.
19. The safety, wages, and statutory payments such as ESI and PF of the workers employed by the contractor for the above work, including those of the contractor himself, shall be the sole responsibility of the contractor. Any expenses incurred by RBDCK in

connection with this work, including accident compensation or litigation costs, shall be recoverable from the contractor.

General Terms

20. RBDCK is not obligated to accept the lowest or any quotation and reserves the right to reject all quotations.
21. For further information, please contact the RBDCK office on working days between 10:00 AM and 5:00 PM (Phone: 0484 2338206, 7034079722)

Quotation

To,

**The General Manager
RBDCK Ltd.**

Sub: Quotation on item rate basis for Planting of Boundary Stones for Edachakkai-Nadakkavu ROB in Kasaragod District -reg.

Sir,

The rate is quoted below:

Sl. No	Item Description	Unit	No .*	Unit Rate (excluding GST)	Total Amount (excluding GST)
1.	Supply and laying Granite/ Concrete stone of size 150 x 150 x 600 mm to be fixed in position using PCC M15 concrete block of size 300mm x 300mm x 450mm embedded in ground, painted using yellow enamel paint, numbered on top in black enamel paint, the name "RBDCK" written on all four sides with black enamel paint,	Nos.	64		
2	<u>Survey Work:</u> Total Station survey for identifying and establishing the boundary stone locations on ground for planting the boundary stones for LA works based on established TBM & approved boundary stone location plan. And submission of as-laid plan of Boundary Stones in CAD format & 3 set of hardcopies (A2 size) with stone number, GPS coordinate, stone to stone distance and showing all affected structures along the alignment.	days	2		
TOTAL					

NB : The cost includes all survey work, material, labour, transportation and conveyance to complete as directed by engineer in charge. Complete. The number of stones is indicative and the payment will be made to actual number of stones laid at site

Yours faithfully

(Signature of Bidder with Name and Address)

Date :

Place :