

RoadsandBridgesDevelopmentCorporationofKeralaLtd.(RBDCK)
(A Government of Kerala Undertaking)
2nd floor, Preethi Building, M.V.Road Palarivattom. Kochi 682025
Phone (484)2338205, 2338206, Fax (91-484) 2533294 Website www.rbdck.com Email: -
rbdckltd@gmail.com

QUOTATION NOTICE

Quotation No. **RBDCK/ R & M/ T 330/ 25/ 2025**

02.09.2025

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for the Repair & Maintenance work of Devadhar ROB in Malappuram District.

- | | |
|-------------------------------------|---|
| 1. Period of completion | - 30 days |
| 2. Date of issue of Schedule | - 02.09.2025 |
| 3. Cost of document | - Free of cost |
| 4. Estimate amount | - Rs. 30.83 lakhs (Approx. Excluding 18% GST) |
| 5. Last date and time of submission | - 09.09.2025, 4.00 PM |
| 6. Opening | - 10.09.2025, 11.30AM |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 02.09.2025, 4.00 PM to 09.09.2025, 04:00 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

Sd/-
General Manager

INSTRUCTIONS TO BIDDERS

1. Printed quotation form can be obtained from the office of the under signed and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc. will be liable for summary rejection.
2. No quotations received after the specified last date and time will be accepted on any account.
3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any.
4. Each Bidder should submit along with the quotation a signed copy of document along with copy of ID proof.
5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities up to 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
7. Time is the essence of the contract. The work shall be completed within 30 days from the date of receipt of written order to commence the work.
8. Contractor shall be solely responsible for any damages occurring to the existing road or any other structures due to this work.
9. Contractor shall appoint qualified engineering representative at site to supervise the work.
10. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other taxes including octroi on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 18% or as decided by the Government from time to time which will be paid in addition to the quoted rates.
11. The Defects liability period for the works is 06 months from the date of completion of the work.

12. The successful bidder shall deposit performance security for an amount equivalent to 5% of the quoted price before executing agreement.
13. In addition to Performance Security, retention money will be deducted from the running/ final bill of the contractor @ 2.5% of the gross amount of each running bill and same shall be released after expiry of defect liability period.

Name and Signature of the Contractor

Tender Inviting Authority: General Manager-RBDOCK Ltd

Work Name:GENERAL- Repair and Maintenance of Devadhar ROB-Repair and Maintenance of Devadhar ROB-General Civil Work-1

Contract No: #####

Name of the Bidder/ Bidding Firm / Company :	
--	--

PRICE SCHEDULE
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, also the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	Sl. No.	TEXT # Item Description	NUMBER # Quantity	TEXT # Units	NUMBER # BASIC RATE in Figures To be entered by the Bidder Rs. P	NUMBER # TOTAL AMOUNT Without Taxes in Rs. P	TEXT # TOTAL AMOUNT In Words
1	1	Road Work	4	5	13	53	55
1.001		2.3.1.A.Cleaning and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 1000 metres including removal and disposal of top organic soil not exceeding 150 mm in thickness. In area of light jungle - By Manual Means OD37/593/2025-2026:Man mazdoor engaged for cutting trees and other cleaning works.	0.017	Hectare		0.00	INR Zero Only
1.002		16.1:Removal of existing cement wearing coat including its disposal complete as per Technical Specification without causing any detrimental effect to any part of the bridge structure and removal of dismantled material with all lifts and lead upto 1000 m	2.000	each		0.00	INR Zero Only
1.003		OD39/107/2025-2026:Cutting and Dismantling of flexible pavements with cutting machine and disposal of dismantled materials up to a lead of 1000 metres, stacking serviceable and unserviceable materials separately
 Bituminous course - By Mechanical Means
	412.500	sqm		0.00	INR Zero Only
1.004		5.2.a:Providing and applying tack coat with bitumen emulsion(RS) using emulsion pressure distributor at the rate of 0.20 - 0.30 kg per sqm on the prepared bituminous surface cleaned with mechanical broom.	60.000	cum		0.00	INR Zero Only
1.005		55.24:Providing and laying bituminous concrete with 80-100 TPH hot mix plant producing an average out put of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder (NRMB) @ 5.4 percent of mix and filler, transporting the hotmix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause NO. 507 complete in all respects (using 7% shredded plastic) Grading - II (13.2 mm nominal size)	1702.500	sqm		0.00	INR Zero Only
1.006		OD49/112/2025-2026:Providing and applying 2 coats of water based cement paint to un plastered concrete surface after cleaning the surface of dirt, dust, oil, grease, efflorescence and applying paint @ of 1 litre for 2 sqm. (Old 14.16)	83.325	cum		0.00	INR Zero Only
1.007		8.8:Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces	2760.000	sqm		0.00	INR Zero Only
1.008		8.13:Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorizing glass beads on Bituminous Surface @ 250 gms per sqm area, the thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform, and free from streaks and holes.	697.000	sqm		0.00	INR Zero Only
1.009		8.35:Providing and fixing reflective road studs (Raised Pavement Marker) of ' category A' made out of ASA/HIPS/ABS moulded body with shanks and conforming to ASTM D 4280, strong enough to support a load of more than 13.635 " when tested in accordance with ASTM D 4280, reflective panel conforming to ASTM D 788, and reflectivity conforming to clause 804.4. Including installation, drilling, fixing with adhesive etc. with 2 years warranty for the road stud as well as for in field performance as per clause 804.7.3 Road Markers/Road Stud with Lense Reflector :-	59.250	sqm		0.00	INR Zero Only
1.011		8.43:Installation of a steel portable barricade with horizontal rail 300 mm wide, 2.5 m in length fitted on a 'A' frame made with 45 x 45 x 5 mm angle iron section, 1.5 m in height, horizontal rail painted (2 coats) with yellow and white stripes, 150 mm in width at an angle of 450, 'A' frame painted with 2 coats of yellow paint, complete as per IRC:SP-55-2001	116.000	no		0.00	INR Zero Only
1.012		8.46:Positioning of a smart flagman with a yellow vest and a yellow cap and a red flag 600 x 600 mm securely fastened to a staff 1 m in length for guiding the traffic	4.000	each		0.00	INR Zero Only
1.013		OD66/450/2025-2026:unforseen items	16.000	each		0.00	INR Zero Only
2		Repair Work of Expansion Joint	1.000	L.S		0.00	INR Zero Only

2.001	OD38679/2025-2026:Removing of Expansion Joints complete as per drawings.	36.000	RM			0.00	INR Zero Only
2.002	14.22:Providing and laying of a strip seal expansion joint catering to maximum horizontal movement upto 70 mm, complete as per approved drawings and standard specifications to be installed by the manufacturer/supplier or their authorised representative ensuring compliance to the manufacturer's instructions for installation	36.000	metre			0.00	INR Zero Only
2.003	OD38683/2025-2026:Furnishing and Placing Micro Concrete after removal of defective concrete and cleaning surface thoroughly - Using Concrete Mixer	5.040	cum			0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words					INR Zero Only		