

**RoadsandBridgesDevelopmentCorporationofKeralaLtd.(RBDCK)**  
(A Government of Kerala Undertaking)  
2<sup>nd</sup> floor, Preethi Building, M.V.Road Palarivattom. Kochi 682025  
Phone (484)2338205, 2338206, Fax (91-484) 2533294 Website  
[www.rbdck.com](http://www.rbdck.com) Email: [-rbdckltd@gmail.com](mailto:-rbdckltd@gmail.com)

**QUOTATION NOTICE**

Quotation No. RBDCK/Mulamkunnathukavu ROB/32/2025

09.10.2025

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for the Demolition of toll booth and Maintenance Works of Mulamkunnathukavu ROB in Thrissur District.

- |                                     |   |                             |
|-------------------------------------|---|-----------------------------|
| 1. Period of completion             | - | 30 days                     |
| 2. Date of issue of Schedule        | - | 09.10.2025                  |
| 3. Cost of document                 | - | Free of cost                |
| 4. Estimate Amount                  | - | 117805.25/- (Excluding GST) |
| 5. Last date and time of submission | - | 15.10.2025, 4.00 PM         |
| 6. Opening                          | - | 16.10.2025, 11.00 AM        |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 09.10.2025 to 15.10.2025 and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

Sd/-  
**General Manager**  
**RBDCK Ltd**

### **INSTRUCTIONS TO BIDDERS**

1. Printed quotation form can be obtained from the office of the under signed and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc. will be liable for summary rejection.
2. No quotations received after the specified last date and time will be accepted on any account.
3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any.
4. Each Bidder should submit along with the quotation a signed copy of document in proof.
5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities up to 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
7. Time is the essence of the contract. The work shall be completed within 30 days from the date of receipt of written order to commence the work.
8. Contractor shall be solely responsible for any damages occurring to the existing road or any other structures due to this work.
9. Contractor shall appoint qualified engineering representative at site to supervise the work.
10. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other taxes including octroi on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 18% or as decided by the Government from time to time which will be paid in addition to the quoted rates.
11. The Defects liability period for the works is 06 months from the date of completion of the work.
12. The successful bidder shall deposit performance security for an amount equivalent to 5% of the quoted price before executing agreement.
13. Retention money will be deducted from the running/ final bill of the contractor @ 2.5% of the gross amount of each running bill and same shall be released after expiry of defect liability period.

Name and Signature of the Contractor

## **SPECIFICATIONS AND SCHEDULE OF WORKS:**

<b>Sl. No</b>	<b>Item</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate</b>	<b>Amount(Rs.)</b>
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 1000 metres including removal and disposal of top organic soil not exceeding 150 mm in thickness   In area of light jungle - By Manual Means 				
		Hectare	0.124		
2	Man Mazdoor engaged for cleaning the drain and other cleaning works				
		No	6		
3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 meters   Cement Concrete Grade M-15 & M-20 - By Mechanical Means  				
		Cum	2.90		
4	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 meters -   Cement Concrete Grade M-15 & M-20. - By Manual Means				
		Cum	1.99		
5	Excavation for roadwork in soil with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location within all lifts and lead up to 1000m				
		Cum	4.80		

6	Construction of granular sub-base by providing graded material, spreading in uniform layers with a motor grader on a prepared surface, mixing by mix in-place method with rotavator at OMC, and compacting with a vibratory roller to achieve the desired density, complete as per clause 401. Grading-V - For sub-base cum drainage layer - Mix in Place Method				
		Cum	2.40		
7	Supplying and laying interlocking tile 100 mm or nearest size thickness, minimum strength M40 including providing a layer of 6 mm aggregate for 5 cm thickness, then laying interlock cobbles in lines and levels as per the directions of the departmental officers at site inclusive of all cost & conveyance charges etc.; complete.				
		Sqm	10.20		
8	Filling Pot-holes with Bituminous shelmac (premix aggregate using cold technology). Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with Bituminous shelmac (premix aggregate using cold technology), compacting, trimming and finishing the surface to form a smooth continuous surface as per the direction of Engineer in Charge				
		Sqm	18.00		
9	Plain/Reinforced Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications   PCC Grade M20 (Without formwork)  				
		Cum	0.42		
10	Supplying and installation of Flexible delineator (Roadway indicators) posts 70-100cm high above ground level, with reflecting tape , and conforming to clause 806 , IRC-79 and including fixing to ground .				
		each	42		
11	Provision of metal drum/empty bitumen drum delineator, 300 mm in diameter, 800 mm high, filled with earth for stability, painted in circumferential strips of alternate black and white 100 mm wide fitted with reflectors 3 Nos of 7.5 cm dia, all as per IRC:SP:55-2001				
		each	6		

12	Providing and pasting High intensity reflective tape of 2 inch size of required color				
		RM	23		
13	Positioning of a smart flagman with a yellow vest and a yellow cap and a red flag 600 x 600 mm securely fastened to a staff 1 m in length for guiding the traffic				
		each	2		
	<b>Total</b>				

Dated Signature of  
Contractor:

Name:

Address: