

**Roads and Bridges Development Corporation of Kerala Ltd. (RBDCK)**  
(A Government of Kerala Undertaking)  
2<sup>nd</sup> floor, Preethi Building, M.V.Road Palarivattom. Kochi 682025  
Phone (484)2338205, 2338206, Fax (91-484) 2533294 Website [www.rbdck.com](http://www.rbdck.com)  
Email: [-rbdckltd@gmail.com](mailto:-rbdckltd@gmail.com)

**QUOTATION NOTICE**

Quotation No. **RBDCK/ Melechovva Flyover/ 85/2026**

**22.05.2026**

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for the construction of the RCC transformer structure in Melechovva, Kannur District. The scope of work consists of earth work for foundation, bottom PCC, RCC work for raft, wall and slab and its reinforcement work, etc.

- |                                     |                                      |
|-------------------------------------|--------------------------------------|
| 1. Period of completion             | - 30 days                            |
| 2. Date of issue of Schedule        | - 22.05.2026                         |
| 3. Cost of document                 | - Free of cost                       |
| 4. Estimate amount                  | - Rs. 87,428 ( excluding 18%<br>GST) |
| 5. Last date and time of submission | - 29.05.2026, 4.00 PM                |
| 6. Opening                          | - 30.05.2026, 11.30AM                |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 22.05.2026, 01.00 PM to 29.05.2026, 04:00 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

**Sd/-**  
**General Manager**

## **INSTRUCTIONS TO BIDDERS**

1. Printed quotation form can be obtained from the office of the under signed and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc. will be liable for summary rejection.
2. Those who wish to participate in the quotation, should fill in the price bid and submit the signed quotation document along with a copy of the photo identity card in a sealed envelope to RBDCK before the specified time. "**Quotation on item rate basis for the construction of the RCC transformer structure in Melechovva, Kannur District "** and do not open before 30.05.2026 at 11:30 AM" should be written on the outside of the cover.
3. No quotations received after the specified last date and time will be accepted on any account.
4. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any.
5. Each Bidder should submit along with the quotation a signed copy of document along with copy of ID proof.
6. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
7. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities up to 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
8. Time is the essence of the contract. The work shall be completed within 30 days from the date of receipt of written order to commence the work.
9. Contractor shall be solely responsible for any damages occurring to the existing road or any other structures due to this work.
10. Contractor shall appoint qualified engineering representative at site to supervise the work.
11. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other

taxes including octroi on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 18% or as decided by the Government from time to time which will be paid in addition to the quoted rates.

12. The Defects liability period for the works is 06 months from the date of completion of the work.
13. The successful bidder shall deposit performance security for an amount equivalent to 3% of the quoted price before executing agreement.
14. In addition to Performance Security, retention money will be deducted from the running/ final bill of the contractor @ 2.5% of the gross amount of each running bill and same shall be released after expiry of defect liability period.

Name and Signature of the Contractor

**SPECIFICATIONS AND SCHEDULE OF WORKS:**

Sl.No	Item	Unit	Quantity	Rate	Amount (Rs.)
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work.   Ordinary soil - Manual Means - (Depth upto 3 M)  	cum	7.774 cum		
2	Plain cement concrete 1:3:6 nominal mix in foundation with crushed stone aggregate 40 mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days.	cum	0.450 cum		
3	Plain/Reinforced Cement Concrete in Open Foundation complete as per Drawing and Technical Specifications.    RCC Grade M30 - Using Concrete Mixer   	cum	1.523 cum		
4	Plain/Reinforced cement concrete in sub-structure complete as per drawing and Technical Specifications RCC Grade M30 - Using concrete Mixer - Height upto 5m	cum	1.768 cum		
5	Supply, Fitting and Placing un-coated HYSD bar Reinforcement in	MT	0.229		

	Foundation complete as per Drawing and Technical Specifications		MT		
6	Supplying, fitting and placing HYSD bar reinforcement in sub-structure complete as per drawing and Technical Specifications	MT	0.265 MT		
<b>TOTAL</b>					

Dated Signature of Contractor:

Name:

*Address:*