

Roads and Bridges Development Corporation of Kerala Ltd. (RBDCK)
(A Government of Kerala Undertaking)
2nd floor, Preethi Building, M.V.Road, Palarivattom, Kochi - 682025
Phone: (484)2338205, 2338206, Fax (91-484) 2533294 Website : www.rbdck.com
Email: -rbdckltd@gmail.com

QUOTATION NOTICE

Quotation No. **RBDCK/R & M/ T 330/ 99/2026**

25.06.2026

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for the Repair & Maintenance work of Sulthanpet ROB in Palakkad District.

- | | |
|-------------------------------------|--------------------------------------------|
| 1. Period of completion | - 15 days |
| 2. Date of issue of Schedule | - 25.06.2026 |
| 3. Cost of document | - Free of cost |
| 4. Estimate amount | - Rs. 1.61 lakhs (Approx.Excluding 18%GST) |
| 5. Last date and time of submission | - 03.07.2026, 4.00 PM |
| 6. Opening | - 04.07.2026,11.30 AM |

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 25.06.2026 to 03.07.2026, 4.00 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

Sd/-
General Manager

INSTRUCTIONS TO BIDDERS

1. Printed quotation forms can be obtained from the office of the undersigned and website of RBDCK. Quotations submitted not in such printed forms or tenders, in complete in any respect such as unattested errors and corrections etc. will be liable for summary rejection.
2. No quotations received after the specified last date and time will be accepted on any account.
3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any.
4. Each Bidder should submit along with the quotation a signed copy of document along with copy of ID proof.
5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.
6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities upto 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.
7. Time is the essence of the contract. The work shall be completed within 15 days from the date of receipt of written order to commencing the work.
8. Contractor shall be solely responsible for any damages occurring to the existing road or any other structures due to this work.
9. Contractor shall appoint qualified engineering representative at site to supervise the work.
10. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales & other taxes including octroi on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 18% or as decided by the Government from time to time which will be paid in addition to the quoted rates.
11. The Defects liability period for the works is 06 months from the date of completion of the work.
12. The successful bidder shall deposit performance security for an amount equivalent to 5% of the quoted price before executing agreement.

13. In addition to Performance Security, retention money will be deducted from the running/ final bill of the contractor @ 2.5% of the gross amount of each running bill and same shall be released after expiry of defect liability period.

Name and Signature of the Contractor

[Validate](#)[Print](#)[Help](#)**Item Rate BoQ**

Tender Inviting Authority: RBDCK

Name of Work: REPAIR & MAINTENANCE OF SULTHAPET ROB IN PALAKKAD DISTRICT

Quotation No. RBDCK/ R & M/ T 330/ 99/ 2026

Name of the Bidder/ Bidding Firm / Company :						
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE in Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1.00	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres &br> Scarping Plaster in Lime or Cement Mortar from Brick/ Stone Masonry &br>	50.000	sqm			
2.00	Construction of sub-grade and earthen shoulders with approved material obtained from borrow pits with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of table No. 300-2	25.000	cum			
3.00	Construction of granular sub-base by providing graded material, spreading in uniform layers with a motor grader on a prepared surface, mixing by mix in-place method with rotavator at OMC, and compacting with a vibratory roller to achieve the desired density, complete as per clause 401. Grading-V - For sub-base cum drainage layer - Mix in Place Method	12.500	cum			
4.00	Providing, laying, spreading and compacting graded stone aggregate to Wet Mix Macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub- base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density.	9.000	cum			
5.00	Supplying and laying interlocking tile 80mm or nearest size thickness, minimum strength M30 including providing a layer of 6mm aggregate for 5cm thickness, then laying interlock cobbles in lines and levels as per the directions of the departmental officers at site inclusive of all cost & conveyance charges etc. complete.	35.000	sqm			
6.00	Laying of dismantled interlocking tile, minimum strength M30 including providing a layer of 6mm aggregate for 5cm thickness, then laying interlock cobbles in lines and levels as per the directions of the departmental officers at site inclusive of all cost & conveyance charges etc - Reusing of dismantled interlocks	15.000	sqm			
Total in Figures						
Quoted Rate in Words						