RoadsandBridgesDevelopmentCorporationofKeralaLtd.(RBDCK)
(A Government of Kerala Undertaking)
2nd floor, Preethi Building, M.V.Road Palarivattom. Kochi 682025
Phone (484)2338205, 2338206, Fax (91-484) 2533294 Website www.rbdck.comEmail: -
rbdckltd@gmail.com

QUOTATION NOTICE

Quotation No. **RBDCK/ R & M/ T 330/ 127/ 2026** **26.11.2026**

On behalf of Roads and Bridges Development Corporation of Kerala Limited, its Managing Director invites sealed quotation on item rate basis for the Repair & Maintenance work of Parappanangadi ROB in Malappuram District.

1.	Period of completion	- 30 days
2.	Date of issue of Schedule	- 26.11.2026
3.	Cost of document	- Free of cost
4.	Estimate amount	- Rs. 4.01 lakhs (Approx. Excluding 18% GST)
5.	Last date and time of submission	- 04.12.2026, 4.00 PM
6.	Opening	- 05.12.2026, 11.30 AM

Quotation forms can be obtained from the office of the undersigned and website of RBDCK from 26.11.2026, 4.00 PM to 04.12.2026, 04:00 PM and interested contractors may obtain further details from RBDCK at the address given above in the office hours.

Sd/-
General Manager

INSTRUCTIONS TO BIDDERS

1. Printed quotation form scan be obtained from the office of the under signed and website of RBDCK. Quotations submitted not in such printed forms or tenders, incomplete in any respect such as unattested errors and corrections etc. will be liable for summary rejection.

2. No quotations received after the specified last date and time will be accepted on any account.

3. Details of the work with item wise specifications are given in the subjoined schedule of work. Bidders must quote only a single rate against each item in the Schedule. The rates quoted shall be inclusive ones covering all the operations contemplated in the schedule of works and all incidental works necessary for such operations. The rate quoted shall not be varied on any account whatever and it shall hold good for all items of work done, irrespective of variations of quantity if any.

4. Each Bidder should submit along with the quotation a signed copy of document along with copy of ID proof.

5. The acceptance of the quotation rests with the officer inviting tenders who does not undertake to accept the lowest or any particular quotation.

6. The quantities shown in the schedule are only approximate and are subject to variation and if found necessary the contractor is bound to do additional quantities up to 25% above estimate quantities of each item of work at his quoted rate. If any extra items of work not included in the schedule are executed, its rates will be arrived at on the basis of the rules followed in Kerala PWD.

7. Time is the essence of the contract. The work shall be completed within 30 days from the date of receipt of written order to commence the work.

8. Contractor shall be solely responsible for any damages occurring to the existing road or any other structures due to this work.

9. Contractor shall appoint qualified engineering representative at site to supervise the work.

10. The rates quoted by the Contractor shall be deemed to be inclusive of the Sales &other taxes including octroi on all materials that the Contractor will have to purchase for performance of this Contract, BUT EXCLUDING GST @ 18% or as decided by the Government from time to time which will be paid in addition to the quoted rates.

11. The Defects liability period for the works is 06 months from the date of completion of the work.

12. The successful bidder shall deposit performance security for an amount equivalent to 5% of the quoted price before executing agreement.

13. In addition to Performance Security, retention money will be deducted from the running/ final bill of the contractor @ 2.5% of the gross amount of each running bill and same shall be released after expiry of defect liability period.

Name and Signature of the Contractor

Validate Print Help

Item Rate BoQ

Tender Inviting Authority: RBDCK

Name of Work: Repair & Maintenance work of Parappanangadi ROB in Malappuram District.

Bid Ref No: RBDCK/ R & M/ T 330/ 127/ 2026

Name of the Bidder/ Bidding Firm / Company :						

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	BASIC RATE In Figures To be entered by the Bidder Rs. P	TOTAL AMOUNT Without Taxes	TOTAL AMOUNT In Words
1	2	4	5	13	53	55
1.001	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, up to a lead of 1000 metres including removal and disposal of top organic soil not exceeding 150 mm in thickness In area of light jungle - By Manual Means	0.067	Hectare		**0.00**	INR Zero Only
1.002	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified material with in all lifts and lead upto 1000 metres by Mechanical Means	280.000	sqm		**0.00**	INR Zero Only
1.003	Supplying and laying interlocking tile 100 mm or nearest size thickness, minimum strength M 40 including providing a layer of 6 mm aggregate for 5 cm thickness, then laying interlock cobbles in lines and levels as per the directions of the departmental officers at site inclusive of all cost & conveyance charges etc.; complete.	280.000	sqm		**0.00**	INR Zero Only
1.004	Filling Pot-holes and Patch Repairs with Bituminous concrete, 40mm. Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504, compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 - For grading I Material	50.000	sqm		**0.00**	INR Zero Only
1.005	Providing and fixing modular rubber speed hump Providing and fixing modular rubber speed hump of approved brand of width 38 cm and height 5cm above finished road surface, including retro reflective reflectors, fixed with bolts & adhesives including fixing charges,site preparation etc complete as per manufactures specifications.	7.500	meter		**0.00**	INR Zero Only
Total in Figures					**0.00**	INR Zero Only
Quoted Rate in Words				**INR Zero Only**		